

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20991-00-00
Spot: SENE Sec/Twnshp/Rge: 5-31S-40W
3352 feet from S Section Line, 641 feet from E Section Line
Lease Name: SHORE EUGENE Well #: 2-5
County: MORTON Total Vertical Depth: 5530 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		WITH 2 SX CMT
PROD	4.5	5497	0	WITH 820 SX CMT
SURF	8.625	1578		WITH 570 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/10/2012 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TRACEY HOLLIS Company: HERMAN L. LOEB, LLC Phone: (719) 340-8987

Proposed Plugging Method: PERFORATE @ 1600' & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2012 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. PERFORATED AT 1600'. PUMPED 400 SX CMT DOWN 4 1/2" CASING WITH 30 SX CMT CIRCULATING TO PIT.

Perfs:

Top	Bot	Thru	Comments
5065	5071		


RECEIVED
OCT 25 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)