

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-189-22636-00-00
 Spot: S2N2NENE Sec/Twnshp/Rge: 9-34S-38W
400 feet from N Section Line, 660 feet from E Section Line
 Lease Name: MORRIS Well #: 9 #1
 County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5278
 Op Name: EOG RESOURCES, INC.
 Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6130		WITH 5 SX CMT
PROD	4.5	6733	1695	WITH 385 SX CMT
SURF	8.625	1654		WITH 480 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/12/2012 9:30 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: ERIC NUNOZ Company: EOG RESOURCES Phone: (405) 246-3100

Proposed Plugging Method: Plug in accordance with KCC rules and regulations. MIRU. Have tubing & casing TIW valves available on/near rig floor. ND tree. NU BOP w/ pipe & blind rams in place. TOOH w/ tubing. TIH w/ 4 1/2" 10M# CIBP on tubing & set @ 6135'. Circulate casing w/ mud. Cap CIBP w/ 5 sx cmt. TOOH. TOOH to 3450'. Spot 20 sx. cmt. to cover DV tool. TOOH. ND BOP & tubing head. Attach pull sub to 4 1/2" casing. If welding is required, fill out Hot Work Permit & use LEL monitor to insure that no flammable gases are present. Pull on casing & unpack slips from wellhead. Set string weight on bottom & release elevators. NU BOP on starting head w/ 4 1/2" pipe & blind rams in place. Work casing for free point. RU WL w/ pack-off & pump in sub. Cut, pull & lay down free pipe. Change out 4 1/2" rams for 2 3/8" rams in BOP. TIH w/ tubing to 1684'. Spot 100 sx. cmt. TOOH. WOC 4 hrs. TIH & tag TOC @ 1604' or higher. TOOH to w/ tubing to 670'. Spot 60 sx. cmt. TOOH to 64'. Spot 20 sx. cmt. to surface. ND

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
 Date/Time Plugging Completed: 10/12/2012 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 6130' WITH 5 SX CMT. 1ST PLUG AT 3450' WITH 20 SX CMT. 2ND PLUG AT 1684' WITH 100 SX CMT. 3RD PLUG AT 700' WITH 60 SX CMT. 4TH PLUG AT 64-0' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6185	6240		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
 OCT 25 2012
 KCC WICHITA

District: 01

Signed Ken Jehlik
 (TECHNICIAN)