

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22325-00-00  
Spot: NENWSENW Sec/Twnshp/Rge: 2-13S-22W  
1400 feet from N Section Line, 1900 feet from W Section Line  
Lease Name: DUANE Well #: 1-2  
County: TREGO Total Vertical Depth: 4169 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1759		180 SX CMT.
PROD	5.5	4147		150 SX
SURF	8.625	222		150 SX
TI	2.375	4126		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2012 8:00 AM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: STEVE STEWART Company: STEWART WELL SERVICE INC Phone: (785) 623-0506

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls and 8 sx gel. DV Tool @ 1759'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/18/2012 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Pulled tubing to 3716'. Pumped 8 sx gel followed by 50 sx cement w/200 # hulls.  
Pulled tubing to 1812' and pumped 125 sx cement.  
Pulled tubing to 920' and pumped 85 sx cement. Good circulation of cement.  
Pulled tubing out. Topped off w/10 sx cement. Hole standing full.  
Tied on to back side. Squeezed w/8 sx cement. Shut in pressure 200 psi.

GPS: 39.54414 -099.73640

Perfs:

Top	Bot	Thru	Comments
3714	3717		


RECEIVED  
OCT 29 2012  
KCC WICHITA

Remarks: QUALITY OILWELL CEMENT

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

OCT 19 2012