

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-30094-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 14-23S-9W
1979 feet from S Section Line, 3432 feet from E Section Line
Lease Name: ROACH Well #: 1
County: RENO Total Vertical Depth: 3747 feet

Operator License No.: 30708
Op Name: C & C TANK SERVICE, INC.
Address: 320 N 3RD
STERLING, KS 67579

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3747		75 SX
SURF	8.625	226		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2012 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: _____

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/17/2012 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3660' - CAPPED WITH 5 SK CEMENT ON TOP. CUT CASING PIPE OFF @ 1812' PULLED CASING TO 1358' SPOTTED 35 SX CEMENT. WAITED 2 HOURS, TAGGED TOP OF CEMENT @ 1160'. PULLED CASING TO 850' SPOTTED 35 SX CEMENT. PULLED CASING TO 270' CIRCULATED TO SURFACE WITH 200 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3725	3728		

RECEIVED
OCT 31 2012
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #C-41053, PAST 10 YEARS NON-PRODUCTION, LOST LEASE.

Plugged through: CSG

District: 02

Signed B. J. Hope
10/17/12 (TECHNICIAN)

TK