

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02692-00-00  
Spot: NESWSWNE Sec/Twnshp/Rge: 7-13S-17W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: CHARLES STAAB Well #: 1  
County: ELLIS Total Vertical Depth: 3556 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3545		200 SX
SURF	8.625	97		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/24/2012 8:45 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Squeezed hole @ 735', 340', 363', 397', 2407', 2469'.  
Rods and tubing ate off in well bore. Could not get on them with overshot.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/24/2012 10:35 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole. Tagged rods and pulled to 1438'. Rigged to tubing and pumped 213 sx cement to circulate cement to pit area. Pulled tubing. Rigged to 5 1/2 casing with a swedge and pumped 43 sx cement to pressure with 200 PSI. Shut in pressure 200 psi. 8 5/8" casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3545	3556		
3302	3472		
3264	3266		
3192	3223		

Remarks: ALLIED OIL AND GAS SERVICES LLC TICKET # 56563

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

OCT 24 2012

RECEIVED  
NOV 02 2012  
KCC WICHITA