

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20031-00-01
Spot: SWNESENW Sec/Twnshp/Rge: 1-15S-19W
3608 feet from S Section Line, 2995 feet from E Section Line
Lease Name: PFANNENSTIEL ANTON Well #: 3
County: ELLIS Total Vertical Depth: 3967 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 300 W DOUGLAS AVE, STE 410
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3698		125 SX
SURF	8.625	208		165 SX

Well Type: EOR UIC Docket No: E16262.2 Date/Time to Plug: 10/25/2012 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: ANDERSON ENERGY INC. Phone: (785) 735-9405

Proposed Plugging Method: Ordered 440 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Superior Perforated: 1850' and 1325'.
Casing leaks @ 2197' - 3329'.
Squeezed @ 555' - 673' w/275 sx cement.
Perforations: 3699' - 3967'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2012 11:10 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole to 3512' and pumped 150 sx cement w/300 # hulls.
Pulled tubing to 2000' and pumped 100 sx cement w/100# hulls.
Pulled tubing to 1000' and pumped 109 sx cement w/100 # hulls to circulate cement to pit area.
Pulled tubing. Topped off 5 1/2" casing with 20 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 15 sx cement with 300 psi. Shut in pressure 300 psi.

GPS: 38.77934 -099.38459

Perfs:

Top	Bot	Thru	Comments
3698	3967		

Remarks: ALLIED CEMENTING TICKET # 56564

Plugged through: TBG

District: 04

Signed [Signature]
11/08/12 (TECHNICIAN)

cc to WCC 11/07/12

CM

RECEIVED

NOV 07 2012

KCC WICHITA