

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
RECEIVED 03/92  
KANSAS CORPORATION COMMISSION

AUG 15 1997  
8-15-97

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-21740 0000 (Identifier number of this well). This well is listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Wilton Jackson/Wilton Petroleum, Inc. KCC LICENSE # 7775  
(owner/company name) (operator's)

ADDRESS 901 King Ave. CITY Nyssa

STATE OR ZIP CODE 97913 CONTACT PHONE # (316)947-3254

LEASE Roemer WELL# 1 SEC. 23 T. 16S R. 30W (EAST/West)

- SW - SW - SE SPOT LOCATION/QQQQ COUNTY Lane

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 209.30 CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 2845/2853 T.D. 4553 PBDT \_\_\_\_\_ ANHYDRITE DEPTH (2244-2269) \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @ 2270' w/50sks)(2nd Plug @ 1300' w/80sks)

(3rd Plug @ 650' w/40sks)(4th Plug @ 230' w/40sks)(5th Plug @ 40' w/10sks)(10sks In Mouse)

(15sks In Rat Hole) Total 245sks 60/40Poz 6%Gel w/1/4#FS/sk By Allied Cementing

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Log IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl Calam PHONE# (316) 947-3254

ADDRESS P.O. Box 315 City/State Hillsboro, Kansas 67063-0315

PLUGGING CONTRACTOR Discovery Drilling, Inc. KCC LICENSE # 31548

ADDRESS P.O. Box 763 Hays, Kansas 67601 (company name) (contractor's)  
PHONE # (913) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8:45 PM 5/16/97

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-15-97 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)