

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-129-2011 <sup>0000</sup> <sub>see</sub> (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Coastal Oil & Gas OPERATORS LICENSE NO. 6593

ADDRESS 1 Leadership Square, 211 N. Robinson, Suite 1700 PHONE # (405) 239-7031

LEASE (FARM) McClain WELL NO. 11-4 WELL LOCATION C NW NW COUNTY Morton

SEC. 4 TWP. 34S RGE. 42W (E) or (W) TOTAL DEPTH 4,757' PLUG BACK TO 4,396'

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 13 3/8" SET AT 123' CEMENTED WITH 175 SACKS

CASING SIZE 8 5/8" SET AT 1231 CEMENTED WITH 400 SACKS

PERFORATED AT 4313'-4319'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @4300' w/10'CMT. Perforate @1230'

Pump & circ 320 sxs; filling 5 1/2" csg & 8 5/8" x 5 1/2" to surface. Cut 4' BGL, wo ident. cap.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? No  
(If not, explain) Not required when well was completed.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-7-91, 7:00 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 1-3-91

John D. Perry PHONE # (405) 239-7031

ADDRESS 211 North Robinson, Suite 1700, Oklahoma City, Oklahoma 73102

PLUGGING CONTRACTOR Dowell-Schlumberger LICENSE NO. N/A

ADDRESS 204 S. Missouri, P.O. Box 887, Ulysses, Ks., 67880 PHONE # (316) 356-1272

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]  
(Operator or Agent)

DATE: 1/1/91

488  
①

Mike Hayden  
Governor

Keith R. Henley  
Chairman

Rich Kowalewski  
Commissioner

Jack Shriver  
Commissioner

Judith McConnell  
Executive Director

Frank A. Caro Jr.  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

January 9, 1991

Coastal Oil & Gas  
1 Leadership Square  
211 N. Robinson, #1700  
Oklahoma City, OK 73102

McClain #11-4  
C NW NW 04-34-42W  
Morton County, KS  
API No. 15-129-20,111 *000*

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

Handwritten signature of David P. Williams in cursive.

David P. Williams  
Production Supervisor

District: #1, 304 W. McArtor  
Dodge City, KS 67801  
(316) 225 - 6760

Conservation Division  
Shari Felst Albrecht  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

Schlumberger

DUAL INDUCTION - LATEROLOG

COUNTY MORTON FIELD or N. TOLOGA LOCATION SEC. 4-34S-42W WELL MC CLAIN NO. 11-4 COMPANY COLORADO OIL CO.	COMPANY	COLORADO OIL COMPANY		
	A.P.I.	15-129-22,111 <del>0000</del>		
	WELL	MC CLAIN NO. 11-4		
	FIELD	N. TOLOGA		
	COUNTY	MORTON	STATE	KANSAS
Location:		C-NW-NW		Other Services:
Sec. 4		Twp. 34S	Rge. 42W	FDC-GR

Permanent Datum: GROUND LEVEL; Elev.: 3407  
 Log Measured From K.B., 10 Ft. Above Perm. Datum  
 Drilling Measured From K.B.

Elev.: K.B. 341  
 D.F. ---  
 G.L. 340

Date	5-25-73					
Run No.	ONE					
Depth-Driller	4757					
Depth-Logger	4757					
Btm. Log Interval	4751					
Top Log Interval	1231					
Casing-Driller	8 5/8 @1231			@	@	@
Casing-Logger	1231					
Bit Size	7 7/8					
Type Fluid in Hole	FGM-CS					
Fluid Level	FULL					
Dens.	Visc.	9.2	60			
pH	Fluid Los	10.0	9.6 ml		ml	ml
Source of Sample	CIRCULATED					
Rm @ Meas. Temp.	1.03 @80 °F	@	°F	@	F	@
Rmf @ Meas. Temp.	0.73 @69 °F	@	°F	@	F	@
Rmc @ Meas. Temp.	--- @ --- °F	@	°F	@	F	@
Source: Rmf	Rmc	M	---			
Rm @ BHT	0.69 @117 °F	@	F	@	F	@
Time Since Circ.	3 HOURS					
Max. Rec. Temp.	117	F	F	F	F	F
Equip.	Location	5105 LIBERAL				
Recorded By	PATTERSON					
Witnessed By	MARDEN					