

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,557-0000

LEASE NAME Cramer

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

3135' Ft. from S Section Line

3630' Ft. from E Section Line

SEC. 22 TWP. 16 RGE. 30 (E) or (W)

COUNTY Lane

LEASE OPERATOR Joseph H. Strabala

ADDRESS 312 E. Uintah St., Colorado Springs, CO. 80903

PHONE# <sup>719</sup>~~303~~ 635-7807 OPERATORS LICENSE NO. 9041

Date Well Completed 9-2-90

Character of Well D & A

Plugging Commenced 9-2-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-2-90

The plugging proposal was approved on August 31, 1990 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Pipe	0	268'	8 5/8	7 jts.	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugs: 2190' 50sks, 1395' 80sks, 700' 50sks, 300' 50sks, 40' 10sks, rat hole 15sks,  
Total 255sks, 60/40 poz, 6% gel, 1lb. flow seal per sk, plug down @ 7:45 A.M. 9-2-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling, Inc. License No. 4083

Address 2700 Oak St., P.O. Box 126, Hays, Kansas 67601

STATE OF Colorado COUNTY OF El Paso, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joseph H. Strabala

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 90

RECEIVED  
STATE CORPORATION COMMISSION  
9-27-90  
SEP 27 1990

Lois E. Bryan  
Notary Public

My Commission Expires: 5/10/94

CONSERVATION DIVISION  
Wichita, Kansas

EFFECTIVE DATE: 8-21-90 State of Kansas

101-21,557-0000

NOTICE OF INTENTION TO DRILL  
Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: 08/21/90 N2SWSE NW Sec 22 Twp 16 S Rg 30 West East West

OPERATOR: License # 9041 3135 feet from South Line of Section  
3630 feet from East Line of Section  
(Note: Locate well on Section Plat on Reverse Side)

Name: JOSEPH H. STRABALA  
Address: 312 E. UINTAH ST.  
City/State/Zip: COLORADO SPRINGS CO 80903  
Contact Person: JOE STRABALA  
Phone: (303) 635-7807

County: LANE  
Lease Name: CRAMER Well# 1  
Field Name: UNKNOWN

CONTRACTOR: License # 4083  
Name: WESTERN KANSAS DRILLING

Is this a Prorated Field? MISSISSIPPI yes XX no  
Target Formation(s): MISSISSIPPI  
Nearest lease or unit boundary: 495  
Ground Surface Elevation: 2780 feet MSL

Well Drilled For: Well Class: Type Equipment:  
XX Oil Inj Infield XX Mud Rotary  
Gas Storage Pool Ext Air Rotary  
OWWO Disposal Wildcat Cable  
Seismic; # of Holes

Domestic well within 330 feet: XX yes XX no  
Municipal well within one mile: XX yes XX no  
Depth to bottom of fresh water: 180  
Depth to bottom of usable water: 1250  
Surface Pipe by Alternate: 1 XX 2  
Length of Surface Pipe Planned to be set: 250  
Length of Conductor Pipe required: \*\*\*\*\*  
Projected Total Depth: 4800  
Formation at Total Depth: MISSISSIPPI  
Water Source for Drilling Operations: XX well XX farm pond XX other

If OWWO; old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp Date: \_\_\_\_\_ Old Total Depth: \_\_\_\_\_

Directional, Deviated or Horizontal Wellbore? XX yes XX no  
Will Cores Be Taken? XX yes XX no  
If yes, total depth location: \_\_\_\_\_  
If yes, proposed zone: 250' Alt. II Req.

Exp. 2/16/91

AFFIDAVIT

Pusher Nancy - 7 Sup Mandy -  
SPUD DATE 8-25-90 INIT. SD

LENGTH SURFACE PLANNED 250'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 5 7/8 @ 268 CONDUCTOR  
ANHYDRITE T- 2128 B- 2186 ELEVATION 2073

TD	FORMATION	RAN PIPE @	DV TOOL	ALT II DONE
		SX	Y	N
	Arbuckle Plug @		Ft. W/	SX
	Hug./Council @		Ft. W/	SX
	Anhydrite Base @	<u>2190</u>	Ft. W/	<u>50</u> SX
	1/2 Base Anhy. @	<u>1345</u>	Ft. W/	<u>80</u> SX
	1/2, 1/2 Plug @	<u>700</u>	Ft. W/	<u>50</u> SX
	Bottom Surface @	<u>300</u>	Ft. W/	<u>50</u> SX
	40' Plug @	<u>40</u>	Ft. W/	<u>10</u> SX
	RAT HOLE CIRC/W	<u>15</u> SX	MOUSE HOLE W/	SX

STATE OF KANSAS  
 RECEIVED  
 SEP 10 1990  
 TECHNICAL CENTER  
 TECHNICIAN CM DATE 8-31-90 Hauling Pond  
 TYPE OF CEMENT 60/40 6" to 2"  
 STARTING TIME 3:30 (AM/PM) DATE 8-29-90  
 COMPLETION TIME 2:45 (AM/PM) DATE 9-29-90  
 CEMENT COMPANY alled