


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 11 Twp. 16 Rge. 14 (E) (W)
Location as "NE/CNW&SW" or footage from lines. SE NE NE¹₄ AUBK
Lease Owner Hinkle Oil Company SE
Lease Name Bitter Well No. # 1
Office Address % Carl Parten
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed yes, by Hinkle Oil Co. 19____
Application for plugging approved yes. 19____
Plugging commenced 2-28-61 19____
Plugging completed 3-4-61 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3361' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>5 1/2"</u>		<u>2,100'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 2-28-61. Plugging completed 3-4-61.

Measured in to total depth: 3361'

Plugged off bottom: Sanded back to 3320' and dumped 5
sacks of cement.

Worked and shot 5 1/2" casing free at 2,100'. Built rack
and slide. Pulled and ~~run~~ laid down casing.

Plugged well: Squeezed well with 10 sacks of mud and
80 sacks of cement (Globe Cement).

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1961
03-15-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 61

My commission expires December 8th, 1963.

Kayann Jenkins
Notary Public.

Casing record.
160' 8"
3348' 5"

WITNESS No 1. NE 1/4 11-16-14W Barton Co. Kansas.
Owner: Minkie Oil Company & Frances Central Oil Co.
Contractor: J. B. Minkie.
Well commenced 12-1-46
Elevation 1917
Well completed 12-13-46

160	190	red rock
590	710	lime
710	915	shale and shells
915	1350	shale
1350	1385	lime
1385	2026	shale and shells
2026	2068	lime
2068	2130	shale
2130	2706	shale and shells
2206	2552	lime
2552	2597	shale and lime
2597	2933	lime
2933	3047	lime and shale
3047	3184	lime
3184	3282	lime and shale
3282	3348	Arb. lime.
3348	3390	

Report

Logging 3140
Arb. 3348

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1951

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas

County of Sedgwick

ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

J. B. Minkie

Subscribed to and sworn to before me this 26th day of December, 1946.

Muriel C. Upton
N. Y.

My commission expires 1-17-50