

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buffington of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co.

Complete Address: P. O. Box 1201, Wichita, Ks.

Lease Name: Suppes Well No. 1- V

Location: SW NE NE Sec. 11 Twp. 16 Rge. (E)(W) 16

County: Rush Total Depth 3524' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buffington was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and
displace 30 sk cmt. Heavy mud to 40' set cementing plug, 1/2 sk hulls
& 15 sk cmt to base of cellar.

Very truly yours,

Rud Z. Massey
Conservation Division Agent