

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Burt of Burt Drdg. Co. has this date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: Hummon Oil, Inc.

Complete Address: 821 Union National Bldg., Wichita, Kansas

Lease Name: Maier Well No. 1

Location: C S/2 NE SE Sec. 24 Twp. 16 Rge. 16 (E)(W) X

County Rush Total Depth 3576 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 450' and
displace 30 sc cement thru drill pipe. Heavy mud to 300' set cementing
plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/3 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Les Massey
Conservation Division Agent

RECEIVED
OCT 70 1966
10-10-66
WICHITA, KANSAS
RECORDED
RECORDED