



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

K13-1975-

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-165-20943-0000

Dear Sir:

Mr. Wilmer Dreiling of Abercrombie Dry has this date requested permission to plug the following described well:

Operator's Full Name: K&E Petroleum, Inc

Complete Address: Hardage Center Suite 300 Wichita Ks.

Lease Name: Schoendallen Well No. 1

Location: NW-SW-SE Sec. 9 Twp. 16 Rge. 18 (E) (W)

County: Rush Total Depth: 3560

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Dreiling was instructed to plug the well as follows:

- 8 5/8" S.P. to 1116' w/ 350 sx Hw. light & 150 sx common
- 1st plug @ 1080' w/ 70 sx 50/50 Poemix 4% gel - 3% c.c.
- 2nd plug @ 540' w/ 40 sx
- 3rd Solid Bridge Build - plug @ 40' → cement 0' w/ 10 sx
- 5th Rathole w/ 5 sx

Very truly yours,

Steve [Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
RCWD  
NOV 23 1981  
11-23-81  
CONSERVATION DIVISION  
Wichita, Kansas