



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Beymer of Beymer & Beymer has this

date requested permission to plug the following described well:

Mr. Beymer guarantees payment of the plugging fee.

Operator's full Name: Beymer & Beymer

Complete Address: Lakin, Kansas

Lease Name: Gardner Well No. # 1

Location: C SW Sec. 10 Twp. 24 Rge. (E) (W) 31

County Finney Total Depth 2699' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Beymer was instructed to plug the well as follows:

7" 360' Circulated w/175 sax.cement.

4 1/2" 2676' Cemented w/50 sax.

Sand hole 2699' to 2650' 5 sax.cement 2650' to 2600'

Mud 2600' to 350' Plug and 35 sax.cement 350' to 250'

Mud 250' to 60' Rock Bridge 60' to 50'

10 sax.cement 50' to Surface.

Very truly yours,

[Signature]
Conservation Division Agent