

API NUMBER 15-165-21,141-

LEASE NAME Victor Werth

WELL NUMBER 110.1

~~4620~~ Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 4 TWP. 16 SRGE. 19W (E) or (W)

COUNTY Rush

Date Well Completed 1-13-84

Plugging Commenced 9-24-84

Plugging Completed 10-8-84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Stecklein Oil Co.

ADDRESS HC #32 Box 384

PHONE# (913) 628-8850 OPERATORS LICENSE NO. 5127

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? ? If not, is well log attached? Yes

Producing Formation K-C Lansing Depth to Top 3340 Bottom 3580 T.D. 3650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	1260	8 7/8	1260	0
		0	3639	5 1/2	3639	2500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged back with sand to 3200 ft. and set a cast iron bridge plug on top of sand. Pulled 2500 ft. of 5 1/2 pipe. Cemented surface with 300 # hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100 # hulls, released plugs, 125 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied cementing Co. License No. none

Address P.O. Box 31, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Ellis, ss.

Daniel Steckli (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Daniel Steckli

(Address) HC #32 Box 384, Hays, Ks.

SUBSCRIBED AND SWORN TO before me this 2 day of November, 19 84

Sherri Underwood
 Notary Public

My Commission Expires: _____

*ACWD
 11-02-84*

