

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2012  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R. 62-3-117

API NUMBER 15-165-20852-00-00

LEASE NAME Oelkers

WELL NUMBER 1

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 4 TWP. 16 S RGE. 19 (E) or (W)

COUNTY Ness

Date Well Completed 3-1-1981

Plugging Commenced 6-24-02

Plugging Completed 6-24-02

LEASE OPERATOR C & L Enterprises, Inc.

ADDRESS P.O. Box 153, Bazine, KS 67516

PHONE (785) 731-5103 OPERATORS LICENSE NO. 31455

Character of Well Oil

(Oil, Gas, O&A, SWD, Inpet, Water Supply Well)

The plugging proposal was approved on 6-24-02 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? No

Producing Formation Kansas City Depth to Top 3339' Bottom 3591' T.D. 3672'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/KC	Oil	3346	3348	8 5/8	416'	None
		3362	3364	4 1/2	3671'	None
		3403	3406			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so: Spot 50 sacks of cement @ 1258', pull to 650' & mix 75 sacks w/ 300# of hulls, cement did not circulate, pull up to 350' & mix 5 sacks of cement with 200# of hulls, pull tubing out of well, top off casing with 10 sacks of cement, pressure 8 5/8 braden head to 500 psi & held. Well plugged.

Name of Plugging Contractor H-D Oil Field Service, Inc. License No. 32970

Address P.O. Box 87, Bazine, KS 67516

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: C & L Enterprises, Inc.

STATE OF Kansas COUNTY OF Ness, ss.

Jeff Werth (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 87, Bazine, KS 67516

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 2002

Bernice Moore  
Notary Public

My Commission Expires: 2/7/06



Form 52-4  
Revised 05-88

OR