

15-165-20440-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Rush \_\_\_\_\_ County. Sec. 2 Twp. 16S Rge. 19W (E) \_\_\_\_\_ (W) X  
Location as "NE/CNW%SW%" or footage from lines. SW NE SW  
Lease Owner Clinton Oil Company  
Lease Name Harold Kuhn Well No. #1 "V"  
Office Address 217 North Water, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed August 11 19 72  
Application for plugging filed August 11 19 72  
Application for plugging approved August 11 19 72  
Plugging commenced August 11 19 72  
Plugging completed August 11 19 72  
Reason for abandonment of well or producing formation D&A



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3625' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1216.35'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud up to  
480'. Cemented with 25 sx.  
Filled hole up to 40'.  
Cemented with 10 sx. Cemented  
rathole with 3 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Co.  
Address 1720 Wichita Plaza, Wichita, Ks. 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Virginia K. Albert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Virginia K. Albert  
1720 Wichita Plaza, Wichita, Ks. 67202  
(Address)

Subscribed and sworn to before me this 16th day of August, 19 72



July 25, 1976

Notary Public.

15.165.20440-0000

DRILLERS LOG

No. 1 "V" Kuhn

CASING RECORD:

8 5/8" @ 1216.35  
w/475 ex cement

TOTAL DEPTH: 3625'

COMPANY: Clinton Oil Co.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: August 1, 1972

COMPLETED: August 11, 1972

DESCRIPTION:

SW NE SW  
2-16S-19W  
Rush County, Kansas


ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sod & Post Rock	0	160
Shale & Sand	160	370
Shale & Sand Streaks	370	655
Sand	655	865
Shale & Redbed	865	1209
Anhydrite	1209	1247
Shale & Redbed	1247	2000
Shale & Lime	2000	3090
Lime	3090	3597
Sand & Lime	3597	3601
Lime	3601	3613
Sand	3613	3625

REMARKS

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.



RED TIGER DRILLING COMPANY

Virginia K. Albert  
Virginia K. Albert

Subscribed and sworn to before me this 16th day of August, 1972.

Barbara L. Spurland  
Notary Public

My Commission Expires:

July 25, 1976