

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,883-00-00

LEASE NAME Reinert

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

2310 Ft. from <sup>N</sup> Section Line

660 Ft. from <sup>W</sup> Section Line

LEASE OPERATOR Hyde-Marrs, Inc.

SEC. 17 TWP. 20 RGE. 23 (XX or (W))

ADDRESS 155 N. Market, #710, Wichita, KS 67202

COUNTY Ness

PHONE 316 ) 262-8339 OPERATORS LICENSE NO. 31231

Date Well Completed 5/27/95

Character of Well D&A

Plugging Commenced 5/27/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/27/95

The plugging proposal was approved on 5/27/95 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4420 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Cons. Div. No.	From	To	Size	Put In	Pulled out
<u>Surface</u>	<u>RECEIVED</u> KANSAS CORPORATION COMMISSION <u>JUL 07 1995</u>	<u>453'</u>	<u>0'</u>	<u>8-5/8"</u>	<u>453'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

plugged with 175 sacks 60/40 Pozmix, 6% gel, 1/4# floseal per sack as follows: 50 sx @ 1480', 40 sx @ 660', 50 sx @ 490', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 10:45 a.m. 5/27/95.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hyde-Marrs, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Thomas C. Hyde

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas C. Hyde

(Address) 155 N. Market, Suite 710 Wichita, KS

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 95

Melinda S. Wooten  
Notary Public

My Commission Expires: 3-12-96

