

15.135-22072-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ness SEC. 18 TWP. 20S RGE. 23W E/W  
Location as in quarters or footage from lines:

C NW SE


Lease Owner Chinook Energy Corporation  
 Lease Name Strecklein #1 Well No. \_\_\_\_\_  
 Office Address 420 Denver Center Bldg. 1776 Lincoln St. Denver, Co.  
 Character of Well (Completed as Oil, Gas or Dry Hole): 80203  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 1-29-82  
 Plugging completed 2-13-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4510'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	323'	none
				4-1/2"	4508'	3346'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 4400' and ran 5 sacks cement. Shot casing @3372' and pulled a total of 85 joints of pipe. Plugged well with 4 sacks hulls, 15 sacks gel, 70 sacks 50/50 pos, 4% gel, 3% cc, 1 sack hulls, 10 sacks gel, 8-5/8" plug, 70 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1982

(If additional description is necessary, use BACK of this record)  
Name of Plugging Contractor Kelso Casing Pulling WICHITA, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 176, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 19 82

My Commission expires:



Irene Hoover  
Notary Public.