

f

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9-14-77

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -165 -20,645 -0000 (of this well)

Operator's Full Name Kansas Oil Corp.

Complete Address 400 N. Woodlawn, Wichita, Kansas

Lease Name Dechant Well No. 1

Location C NW Sec. 23 Twp. 16 Rge. (E) (W) 18

County Rush Total Depth 3373'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Big Springs Drlg.

Address Great Bend, Kansas License No.       

Operation Completed: Hour 1:20 P Day 13 Month 9 Year 1977

The above well was plugged as follows:

RTD 3373' 8 5/8 csg set 420' cwc 225 sk. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Geo Marney  
Well Plugging Supervisor

DATE 9-14-77  
INV. NO. 5843-W