

15.165-20397-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 7 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Misco Industries, Inc.

Complete Address Misco Bldg., Wichita, Kansas 67202

Lease Name Herman "A" Well No. 1

Location C: ~~E~~ E/2 NE Sec. 22 Twp. 16 Rge. (E) (W) 18

County Rush Total Depth 3583'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor SW Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11 A Day 6 Month 11 Year 1974

The above well was plugged as follows:

Total depth 3583' 8 5/8 csg set at 252' cwc 160 sk.

5 1/2 csg set at 3531' cw 125 sk cmt.

Set 5 1/2 wood plug at 3000' -poured 10' sand -dumped 4 sk cmt W/dump bailer. (3000-2960)

Cutoff & recovered 2305' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

& pumped 125 sk 50-50 poz 6% by Allied. PP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russ F. Massey  
Well Plugging Supervisor

DATE 11/18/74

INV. NO. 266-W