

15-165-30133-00-01

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. C. Davis

Complete Address: 304 Insurance Bldg., Wichita, Kansas 67202

Lease Name Legleiter Well No. 1

Location C NW NE Sec. 16 Twp. 16 Rge. 18 (E) (W) X

County Ellis Rush Total Depth 3610

Abandoned Oil Well Gas Well Input Well SWD Well D & A X (OWWO)

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12 N Day 29 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 3610' 8 5/8 csg set at 1133' cwc.

5 1/2 csg set at 3609' cw 100 sc cement.

5 1/2 csg perf. 3590-95.

Filled 5 1/2 csg with sand to 3580' and dumped 5 sc cement with dump bailer.

Recov. 2928' of 5 1/2 csg.

Mud to 520' set rock bridge (520-500)

Filled with 7 yds readymix cement (500 to surface.)

I hereby certify that the above well was plugged as herein stated.

Signed: R. J. Manning
Well Plugging SupervisorINVOICED
DATE 6/4/68
INV. NO. 7845-W