

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 95-12 Location: NW NW NW  
County: Rush Sec. 13 Twp. 16 Rge. (E) (W) 18  
Name of Field or Pool: \_\_\_\_\_ Total Depth: 3673

I have this date completed supervision of plugging of:

Well No. 1-A Lease Herman  
Operator's Full Name Aylward Drg Co  
Complete Address: 813 1st Natl Bk Wichita, Kans  
Plugging Contractor: West Supply Co  
Address: Chase, Kans License No. 14  
Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_  
If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 1 Month 5 Year 58

The above well was plugged as follows:

8 5/8" at 1135' circulated with cement. 5 1/2" 3672' with 12s sax cement  
behind-Perforated 3420 after P.B. to 3445'.  
Filled with sand to 3400', set 4 sax cement with dump bailer, pulled  
2900' 5 1/2" - filled hole with heavy chunk mud to 400', set 15 sax cement,  
heavy chunk mud to 200', set 15 sax cement, heavy mud to 35', set rock  
and 10 sax cement to bottom cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: [Signature]  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
5-6-58  
MAY 6 1958

Reviewed: [Signature]  
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

PLUGGING  
FILE NO. 13 T. 16 R. 18 E  
BOOK PAGE 96 LINE 13