

15101 20065 0000

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
SEP 19 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Hinkle Oil Company,

Complete Address 1016 Union Center, Wichita, Kansas.

Lease Name Dickey Well No. 1

Location NW-SE-NE Sec. 25 Twp. 16 Rge. (E) (W) 30

County Lane Total Depth 4590'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling Company,

Address Box #176, Chase, Kansas. License No. 670

Operation Completed: Hour 2:00 PM Day 13 Month 9 Year 1974

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 180 Sx.

4559'--5 1/2" Production casing cemented on bottom with 275 Sx. Well plugged back to

4525'. Top of perforations @ 4437'.

Pushed plug to 4400', sanded well back to 4350' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (1500') and squeezed well initially with 5 sacks hulls and 15 sacks

gel and followed with 110 Cu. Ft. cement from 1050' to 725' then 10 sacks gel from

725' to 325' and followed with 30 Cu. Ft. cement from 325' to 250' then 5 sacks gel

from 250' to 40' and finally 10 Cu. Ft. cement from 40' to base of cellar. Maximum

pump-in pressure-500#. FSIP-200#. (Mudding and cementing by Allied Cmtg., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed:

Well Plugging Supervisor

INVOICED

DATE 9/24/74
INV. NO. 9948-W