

15165-20409-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco Industries, Inc.

Complete Address Misco Bldg., Wichita, Kansas 67202

Lease Name Leo Kreutzer Well No. 1

Location C S/2 NE Sec. 26 Twp. 16 Rge. (E) (W) 18

County Rush Total Depth 3400'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1:15 P Day 6 Month 11 Year 1974

The above well was plugged as follows:

Total Depth 3400' 8 5/8 csg set at 243' cwc 160 sk.

4 1/2 csg set at 3399' cw 175 sk cmt.

Filled 4 1/2 csg W/sd 3400-3000 -dumped 4 sk cmt W/dump bailer. (3000-2970)

Cutoff & eacovered 2505' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug &

pumped 125 sk 50-50 poz 6% by Allied. PP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo I. Massey
Well Plugging Supervisor

DATE 11/8/74

INV. NO. 267-W