

15-135-21104-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

10-31-75
10-31-75

Operator's Full Name Slawson Drilling Company, Inc.
Complete Address 408 One Twenty Bldg., Wichita, Kansas
Lease Name Foos "F" Well No. 1
Location C NE NE Sec. 11 Twp. 20 Rge. (E) (W) 23
County Ness Total Depth 4450'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.

Operation Completed: Hour 8:45 P Day 29 Month 10 Year 1975

The above well was plugged as follows:

RTD 4450' 8 5/8 csg set 443' cwc 250 sk. Flg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.
Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/31/75

INV. NO. 2160-W