

15-165-00151-0000

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Murfin Drg Co
Complete Address: 617 Union Center Wichita, Kansas
Lease Name Lohrey Well No. 1
Location NE NE SE Sec. 29 Twp. 18 Rge. (E) (W) 16
County Rush Total Depth 3682
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kansas License No. 2
Operation Completed: Hour 4PM Day 6 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 1097' Circulated with cement - 5 1/2" 3682' with 125 sax cement -
PB to 3672' - perf 3661'
Filled with sand to 3650', set 4 sax cement with dump bailer - pulled 2000'
5 1/2" - filled hole with heavy gel mud to 480' (10 sax Gel), set rock bridge
to 450' - filled hole with 6yds Ready-mix 450' to 0' (2500 formula)

RECEIVED

STATE CORPORATION COMMISSION

JUL 10 1962

7-10-62

CONSERVATION DIVISION

Wichita, Kansas

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 7/10/62

INV. NO. 5347-W

Signed: Edwin Peery
Well Plugging Supervisor