

15-159-20349 - 00-00

Form CP-3
Rev. 6-4-68

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Northridge Oil Company

Complete Address P.O. Box 18271, Denver, Colorado 80218

Lease Name Keeley Well No. 1

Location NW SW SW Sec. 18 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3454'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour 5 PM Day 5 Month November Year 1971

The above well was plugged as follows:

Hole filled with sand to 3440' and cemented with 5 sacks cement.

Hole filled with mud to 215'. Rock bridge set from 215' to 200' and hole cemented

with 35 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30'

and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: *Arthur J. Lomen*
Well Plugging Supervisor

DATE 11-11-71

INV. NO. 4600-4