

1 060034

9-2

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION. N/2 SW SE NW SEC. 22, T 16 S, R 30 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,557-0000  
3135 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9041

Lease Name Cramer Well # 1

Operator: Joseph H. Strabala  
Name & Address: 312 E. Uintah St.  
Colorado Springs, CO 80903

County Lane  
Well Total Depth 4550 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 268

147.87

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Western Kansas Drilling License Number 4083

Address P.O. Box 126, Hays, KS 67601

Company to plug at: Hour: 3:30 p.m. Day: 2 Month: 9 Year: 19 90

Plugging proposal received from Jim Manly

(company name) Western Kansas Drilling (phone) 913-628-2296  
Elevation 2073'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2158-86'

1st plug at 2190' with 50 sx cement, 2nd plug at 1395' with 80 sx cement,  
3rd plug at 700' with 50 sx cement, 4th plug at 300' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:45 p.m. Day: 2 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement,  
2nd plug at 1395' with 80 sx cement,  
3rd plug at 700' with 50 sx cement,  
4th plug at 300' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-10-90  
SEP 10 1990

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: SEP 18 1990

Signed [Signature] (TECHNICIAN)

INV. NO. 29359