

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-14- 20 794-0000

NE NE SW, SEC. 23, T 16 S, R 30 W/B R

330 FEET FROM N/S SECTION LINE

480 FEET FROM W/E SECTION LINE

LEASE NAME Roemer WELL # 1

COUNTY LANE

WELL TOTAL DEPTH 4580 FEET \$148.85

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 329'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MURFIN Drilling Co. LICENSE NUMBER 6033

ADDRESS 617 Union Center Wichita Ks 67202 Rig tag # 608

COMPANY TO PLUG AT: HOUR: 4:30 pm DAY: 23 MONTH: June YEAR: 19 83

PLUGGING PROPOSAL RECIEVED FROM None Received, Bernie Meyers

(COMPANY NAME) MURFIN Drilling Co (PHONE) _____

WERE: use 60/40 Pos mix, 2% Gel, 3% C.C.

1st Plug @ 2250' w/50 sx cmt circulate 15 sx cmt

2nd Plug @ 1710' w/50 sx cmt 1 v Rat hole,

3rd Plug @ 390' w/40 sx cmt

4th 40-0 w/SBP + 10 sx cmt.

PLUGGING PROPOSAL RECEIVED BY Benny E Beck
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 8:15 pm DAY: 23 MONTH: June YEAR: 19 83

ACTUAL PLUGGING REPORT _____

Plugged as purposed above per Bernie Meyers
Phone 6-24-83.

Haliburton did the cementing.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1983

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: GL Elevation 2481' Anhydrite Top 2243'

I (~~did~~) DID NOT OBSERVE THIS PLUGGING.

SIGNED Benny E Beck
(TECHNICIAN)

INVOICED
DATE 7-7-83
INV. NO. 4756-W

FORM CP-2/3
REV. 6-83