

1-060346

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,043-0000

SE NE NE, SEC. 23, T 16 S, R30 W/R
N SE Corner of
4440 feet from NXX section line
W SE Corner of
330 feet from MXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Bentley Well # 1-23

Operator: Gear Petroleum Co., Inc.

County Lane

Name & Address 300 Sutton Place

Well Total Depth 4570 148.53 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 316

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 24 Month: September Year: 19 84

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2215' with 50 sx cement

2nd plug at 1650' with 70 sx cement

3rd plug at 365' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: midnight Day: 24 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2215' with 50 sx cement, 2nd plug at 1650' with 70

sx cement, 3rd plug at 365' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

10-1-84
OCT 01 1984

Don Ubel gave these plugging orders

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

Signed Paul A. Luthi (TECHNICIAN)

INVOICED

DATE 10-5-84

INV. NO. 4050 9-24