

To: 1 070002 5-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-101-21,740-0000

SW SW SE, SEC. 23, T 16 S, R 30 W/E
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7775

Lease Name Roemer Well # 1
County Lane 147.97

Operator: Wilton Petroleum, Inc.
Name & Address: 901 King Ave.
Nyssa, OR 97913

Well Total Depth 4553 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Discovery Drilling, Inc. License Number 31548
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 4 p.m. Day: 16 Month: 5 Year: 19 97

Plugging proposal received from Tom Alm
(company name) Discovery Drilling, Inc. (phone) 913-623-2920

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2244-69'
1st plug at 2269' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,
3rd plug at 230' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:45 p.m. Day: 16 Month: 5 Year: 19 97
1st plug at 2269' with 50 sx cement,

ACTUAL PLUGGING REPORT
2nd plug at 1300' with 80 sx cement,
3rd plug at 230' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

5-21-97
MAY 21 A 2:12

Remarks: Used 60/40 Pozmix 6% gel 1/2# flow seal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 5-27-97

Signed _____ (TECHNICIAN)

INV. NO. 48176 5-16 JUL 22 1997