

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21559-00-00
Spot: N2SWNW Sec/Twnshp/Rge: 26-31S-8W
1650 feet from N Section Line, 660 feet from W Section Line
Lease Name: AGNEW A Well #: 1-26
County: HARPER Total Vertical Depth: 4789 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4747		
PKR		4339		
PROD	5.5	4790	2960	150 SX
SURF	8.625	220		225 SX
T1	2.875	4339		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/06/2012 8:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: CIBP 4312 & 2 SKS, REC CASING. 1350' 35 SX, 900' 35 SX, CIRC CEMENT 270'-0'.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 09/06/2012 3:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4312' & CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 2960' AND PULLED TO 1350' WHERE 35 SX OF CEMENT WAS SPOTTED. PULLED CASING TO 900' & SPOTTED 35 SX CEMENT. PULLED CASING TO 270' AND CIRCULATED CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4369	4377	CSG	MISSISSIPPIAN
4362	4620	CSG	

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 02

Signed


10/18/12 (TECHNICIAN)

RECEIVED
KANSAS CORPORATION
OCT 01 2012
CONSERVATION DIVISION
WICHITA, KS