

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-10030-00-01
Spot: SWSENE Sec/Twnshp/Rge: 5-30S-8W
2970 feet from S Section Line, 4290 feet from W Section Line
Lease Name: POMEROY GU (OWWO) Well #: 3
County: KINGMAN Total Vertical Depth: 4282 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 4280 | 2140 | |
| SURF | 8.625 | 310 | | |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/12/2012 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 4080' & 4 SKS. REC PIPE, 1250' 35 SX, 850' 35 SX, 360' & CIRCD TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/12/2012 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4080' & CAPPED WITH 4 SKS CMT.
THE CASING WAS RECOVERED FROM 2140' & PULLED TO 1250' WHERE 35 SX OF
CEMENT WAS SPOTTED. PULLED CASING TO 850' & SPOTTED 35 SX OF CMT.
PULLED CASING TO 360' & CIRCULATED CEMENT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4140 | 4234 | CSG | |

Remarks: QUALITY WELL SERVICE #5671 60/40 4% GEL.

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)
10/18/12

RECEIVED
KANSAS CORPORATION
OCT 01 2012
CONSERVATION DIVISION
WICHITA, KS