

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-28286-00-00

Spot: NWNWNESE

Sec/Twnshp/Rge: 2-24S-14E

2805 feet from N Section Line,

1251 feet from E Section Line

Lease Name: VERNON FEE

Well #: 1

County: WOODSON

Total Vertical Depth: 1673 feet

Operator License No.: 34762

Op Name: JAMES PRODUCTION, INC.

Address: 1334 GROUSE RD

YATES CENTER, KS 66783

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
<u>SURF</u>	<u>8.625</u>	<u>40</u>		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/29/2012 12:00 AM

Plug Co. License No.: 30567

Plug Co. Name: RIG 6 DRILLING CO., INC.

Proposal Rcvd. from:

Company:

Phone:

Proposed
Plugging
Method:

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 08/29/2012 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran drill pipe to TD. Mixed and pumped gel through the drill pipe at TD. Pumped 15 sacks of cement through the drill pipe at TD. Pulled drill pipe up to 947'. Pumped 15 sacks of cement through the drill pipe at 947'. Pulled drill pipe up to 200'. Circulated cement through the drill pipe from 200' to surface. Pulled remaining drill pipe and topped well off with cement. A total of 90 sacks of portland cement was reported used to plug this well.

RECEIVED

SEP 26 2012

KCC Chanute Dist. #3

RD

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 01 2012

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: DP

District: 03

Signed

(TECHNICIAN)