

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21383-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 36-30S-7W
760 feet from S Section Line, 560 feet from W Section Line
Lease Name: RUSSELL Well #: 2
County: KINGMAN Total Vertical Depth: 4775 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		
PROD	5.5	4773	1325	200 SXS CMT
SURF	8.625	355		300 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2010 12:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: JERRY DUNKIN Phone: (580) 237-6152

Proposed Plugging Method: CIBP 4300 & 2 SKS. 35 SX 1300', 35 SX 750' CIRC 400'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 12/13/2010 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4290' & CAPPED WITH 2 SKS CEMENT. CASING RECOVERED FROM 1325'. RAN TUBING TO 1300' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 750' AND SPOTTED 35 SX CEMENT. PULLED TUBING TO 400' & CIRCULATED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4748	4750	CSG	
4726	4730	CSG	
4343	4355	CSG	

Remarks: JERRY DUNKIN INC. COM CEMENT

Plugged through: TBG

District: 02

Signed _____ (TECHNICIAN)
10/18/12

RECEIVED
OCT 05 2012
KCC WICHITA