

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22434-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 18-34S-12W
627 feet from N Section Line, 555 feet from E Section Line
Lease Name: J V COOK Well #: 18-1
County: BARBER Total Vertical Depth: 6411 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S VOSS RD STE 600
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4460		WITH 2 SX CMT
CIBP		4770		
PROD	4.5	4918	3300	WITH 175 SX CMT
SURF	13.375	330		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/21/2012 9:00 AM
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.
Proposal Rcvd. from: BILL SCHMIDT Company: SCHMIDT ENGINEERING Phone: (316) 772-0921

Proposed Plugging Method: SET CIBP @ 4460' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 100 SX CMT. PLUG AT 60' WITH 40 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2012 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4460' & 2 SX CMT. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 340' WITH 100 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4715	4730		
4704	4710		

RECEIVED
OCT 09 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
OCT - 2 2012
KCC DODGE CITY

Signed Stephen J. Gardner
(TECHNICIAN)