

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23261-00-00
Spot: SENESWNW Sec/Twnshp/Rge: 12-19S-11W
1810 feet from N Section Line, 1160 feet from W Section Line
Lease Name: RINGWALD Well #: 4
County: BARTON Total Vertical Depth: 3410 feet

Operator License No.: 33288
Op Name: MANNING, GREGORY
Address: 574 SE 130 AVE
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3409		150 SX
SURF	8.625	241		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2012 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GREGORY MANNING Company: GREGORY MANNING Phone: (620) 564-2360

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cut casing @ 1675' leaving 1734' of 5 1/2 " casing in hole.
Set CIBP plug @3000'.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2012 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Pulled casing to 1250'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 850'. Pumped 50 sx cement w/100 # hulls.
Pulled casing to 500'. Pumped 40 sx cement w/100 # hulls.
Pulled casing to 200'. Pumped 70 sx cement w/50 # hulls. Cement circulated, but fell back.
Pumped additional 20 sx cement to fill cellar. Total of 90 sx cement pumped @ 200'.
POOH. Cellar stayed full of cement.
Checked TOC 09/21/2012. 25' to 30' down. Will fill and cover w/cellar.

Perfs:

Top	Bot	Thru	Comments
3340	3343		
305	3088		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING INC. TICKET # 53738

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
10/18/12

(TECHNICIAN)

CM

SEP 24 2012