

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21620-00-00
Spot: SESENW Sec/Twnshp/Rge: 9-12S-22W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RINKER Well #: 22-9
County: TREGO Total Vertical Depth: 4097 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1868		425 SX
PROD	4.5	4097		150 SX
SURF	8.625	250		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2012 9:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: _____ Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 623-8120

Proposed Plugging Method: DV tool @ 1868' w/425 sx cement.
Perforations @ 4009' and 4032'.
Ordered 425 sx 60/40 pozmix 4% gel cement w/400 # hulls

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2012 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3646'. Pumped 100 sx cement w/400 # hulls.
Pulled tubing to 2606' and pumped 100 sx cement w/200 # hulls. Good circulation of cement.
Pulled tubing out. Topped off with 30 sx cement. Hole standing full.
Tied on to back side and squeezed with 15 sx cement. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
4009	4032		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET # 37179

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

CM

OCT 02 2012