

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21110-00-00  
Spot: W2SWNE Sec/Twnshp/Rge: 31-17S-10W  
3300 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: GRIZZELL Well #: 24  
County: ELLSWORTH Total Vertical Depth: 3248 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3243		125 SXS CMT
SURF	8.625	330		200 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2012 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-8088

Proposed Plugging Method: WILL PLUG ACCORDING TO INSTRUCTIONS BY KCC.

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/27/2012 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 2900' & CAP WITH 5 SX'S CEMENT. PERFORATE AT 1400', 1075' & 380'. RUN TUBING TO 1400' & PUMP 35 SX'S CEMENT, PULL TUBING TO 1075' & PUMP 35 SX'S, PULL TUBING TO 380' & CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT & TOP OFF. USED 200 SX'S.

Perfs:

Top	Bot	Thru	Comments
3248			OH OPEN HOLE

RECEIVED  
OCT 10 2012  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #7199. COPELAND TICKET C-39134 DENIED TA - HFLD

Plugged through: TBG

District: 02

Signed Virgil Clothier  
10/10/12 (TECHNICIAN)