

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20636-00-00  
Spot: SWNESESW Sec/Twnshp/Rge: 23-34S-20W  
669 feet from S Section Line, 2043 feet from W Section Line  
Lease Name: MARLENE Well #: 1-23  
County: COMANCHE Total Vertical Depth: 5450 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5130		WITH 2 SX CMT
CIBP		5400		
PROD	5.5	5449	1910	WITH 150 SX CMT
SURF	8.625	736		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2012 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 5130' WITH 2 SX CMT. PLUG AT 750' WITH 12 SX GEL & 50 SX CMT. PLUG AT 270' WITH 30 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/02/2012 10:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SEST CIBP @ 5130' WITH 2 SX CMT. 1ST PLUG AT 773' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 279' WITH 30 SX CMT. 3RD PLUG AT 58' WITH 30 SX CMT. TOPPED OFF WITH 15 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5180	5300		

RECEIVED  
OCT 11 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
OCT - 8 2012  
KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)

RAW