

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-24122-00-00
Spot: NESENWNE Sec/Twnshp/Rge: 24-25S-21E
700 feet from N Section Line, 1600 feet from E Section Line
Lease Name: BLYTHE Well #: 2
County: BOURBON Total Vertical Dept: ██████████

Operator License No.: 34581
Op Name: MACHA ENTERPRISES, INC.
Address: PO BOX 220
GAS, KS 66742

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2012 11:30 AM
Plug Co. License No.: 5786 Plug Co. Name: MCGOWN DRILLING, INC.
Proposal Rcvd. from: CHRIS MCGOWN Company: MCGOWN DRILLING, INC. Phone: (620) 224-7406

Proposed Plugging Method: Mix and pump gel. 10 sacks at TD, 10 sacks at 600', cement from 250' to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 09/07/2012 11:30 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Mixed and pumped gel through the drill stem at TD. Pumped 10 sacks of cement through the drill stem at TD. Pulled drill stem up to 600'. Pumped 10 sacks of cement through the drill stem at 600'. Pulled drill stem up to 250'. Pumped and circulated cement through the drill stem from 250' to surface. Pull the rest of the drill stem out of the well and topped the well off with cement. A total of 48 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

OCT 10 2012

KCC Chanute Dist. #3

RD

RECEIVED

OCT 12 2012

KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed

[Signature]
10/18/12 (TECHNICIAN)