

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00267-00-00
Spot: N2 Sec/Twnshp/Rge: 4-25S-35W
4016 feet from S Section Line, 2681 feet from E Section Line
Lease Name: SHIELDS Well #: 1
County: KEARNY Total Vertical Depth: 2701 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	2296	1766	ON AD-1 PACKER NO CMT
PROD 7		2603	0	WITH 1000 SX CMT
SURF 10		650		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/25/2012 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2012 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SANDED BACK TO 2350'. BAILED 12 SX CMT ON TOP OF SAND. TAGGED CMT AT 2214'. 1ST PLUG RAN TBG TO 1766' & SPOTTED 50 SX CMT. 2ND PLUG PULLED TBG TO 1100'. PUMPED 50 SX CLASS C CMT W/2% CC WITH 100# HULLS MIXED IN. WAITED 2 HOURS & TAGGED PLUG AT 840'. PRESSURE TESTED CASING FROM 840' TO 0' AT 600 PSIG. BOND LOGGED 7". FOUND CMT FROM 840' TO 310' & 62' TO 0'. 3RD PLUG RAN TBG TO 840' & CIRCULATED CMT TO SURFACE WITH 150 SX CMT. PULLED TBG OUT & TOPPED OFF HOLE WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2355	2598		

RECEIVED
OCT 15 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed: [Signature] (TECHNICIAN)

RECEIVED

OCT - 8 2012

KCC DODGE CITY