

15-165-30010-0000

9

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bill Hay Drilling Co., Inc.
Complete Address: c/o George Welling Paradise, Kansas 67685
Lease Name Schutte Well No. 1
Location C NW NW Sec. 6 Twp. 16 Rge. (E) (W) 19
County Rush Total Depth 3695
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:
Plugging Contractor: Co. Tools HOWCO
Address: Paradise, Ks. License No.
Operation Completed: Hour 12N Day 16 Month 5 Year 1969

The Above well was plugged as follows:
Total Depth 3695' 8 5/8 csg set at 312' cwc
5 1/2 csg set at 3680 PBD (3675) Perf. (3614-3650) No pipe recovered
(5-14-69) Displaced thru 2" tubing 25 sk cmt (3500-3695)
Pulled tubing packer to 720 where bad casing hung packer. Unscrewed tubing from packer.
Pumped thru 5 1/2 swage with 150 sk cmt. SI pres. 200 lbs.
Annulus (8 5/8-5 1/2) would not take fluid.
(5-16-69) Run wire line to top of cement. (50') Cut off 5 1/2 and 8 5/8 csg and filled
to surface with cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo P. Massey
Well Plugging Supervisor

INVOICED

DATE 5-19-69
INV. NO. 9788-W