

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dreiling Oil, Inc.

Complete Address Route 2 Victoria, Kansas 67671

Lease Name Brown Well No. 1

Location NW NW NW Sec. 21 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address Victoria, Kansas License No.

Operation Completed: Hour 9 P Day 10 Month 7 Year 1971

The above well was plugged as follows:

RTD 3860' 8 5/8 csg set at 231' cwc 150 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Bus J. M...*
Well Plugging Supervisor

INVOICED

DATE 7/12/71

INV. NO. 3975-W