

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

AUG 22 1978

8-22-78

CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165 - 20,688-0000 (of this well)

Operator's Full Name F & M Oil Co., Inc.

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Dreher Well No. 1

Location SE NW NE Sec. 23 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Woodman-Iannitti Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1:45 A Day 21 Month 8 Year 1978

The above well was plugged as follows:

RTD 3700' 8 5/8 csg set 300' cwc 185 sk. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Red Massey
Well Plugging Supervisor

INVOICED

DATE 8-23-78

INV. NO. 1909-W