

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-165-21, 021-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name WALTERS AND WALTERS

Complete Address 5924 ROYAL LANE - #155 DALLAS, TEXAS 75230

Lease Name SCHAFFER Well No. #1

Location NE-NE Sec. 8 Twp. 16 Rge. 19 (East)(West)

County RUSH Total Depth 3715 <sup>ft</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor PIONEER DRILLING INC. (TOM ALM)

Address 308 WEST MILL PLAINVILLE, Mo. 67663 License No. \_\_\_\_\_

Operation Completed: Hour: 9:00 PM Day: 7<sup>th</sup> Month: SEPT Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 208<sup>ft</sup> SP. OUC. w/ 125<sup>st</sup> 60% FORMIX - 2% GEL - 3% CA-CL. (ALLIED CNT.)  
ORDERED 160<sup>st</sup> 50% FORMIX 4% GEL - 3% CA-CL. AND 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS  
1<sup>st</sup> Plug @ 720<sup>ft</sup> w/ 100<sup>st</sup> CNT.  
2<sup>nd</sup> Plug @ 270<sup>ft</sup> w/ 40<sup>st</sup> CNT.  
3<sup>rd</sup> Plug -> SOLID BRIDGE HULL'S - PLUG @ 40<sup>ft</sup> to 10<sup>st</sup> CNT.  
10<sup>st</sup> IN RAT HOLE. (CIRCULATE)

CEMENTED BY ALLIED CNT.

Amount of Surface Casing: 208<sup>ft</sup>

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

SEP 14 1982

INVOICED  
DATE 9-27-82  
INV. NO. 1278-W  
Conservation Division Agent  
Wichita, Kansas