

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Co.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas

Lease Name Michaels Well No. 1

Location NE SE NE Sec. 13 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 8:30 A Day 12 Month 12 Year 1973

The above well was plugged as follows:

RTD 3680' 8 5/8 csg set at 246' cwc 160 sk.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 12/14/73
INV. NO. 8296-W