

15-165-20503-0000

~~KANSAS~~

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
STATE CORPORATION COMMISSION
RECEIVED
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 435 Page Ct., 220 W. Douglas, Wichita, Kansas

Lease Name Little Well No. 1

Location SW NW SE Sec. 20 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 17 Month 7 Year 1974

The above well was plugged as follows:

RTD 3890' 8 5/8 csg set at 255' owe 175 sk. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 240' displaced 20 sk cmt plug thru drill pipe. Heavy mud to 40' set

cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7/23/74
INV. NO. 9583-W