



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Rec'd
 10-21-63

Dear Sir:

Mr. Bob Sargent of Sargent's Csg. Pulling Co. has this date requested permission to plug the following described well:
Publishers Petroleum Co.
 Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Publishers Petroleum Company,

Complete Address: 500 North Broadway, Oklahoma City, Oklahoma.

Lease Name: Kelly Unit Well No. 1

Location: NW-SE Sec. 5 Twp. 19 Rgs. (E) (W) 40

County Greeley Total Depth 2940 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

174'--8 5/8" Surface pipe, cement circulated.
2940'--4 1/2" cemented with top perforations @ 2933'.

Squeeze bottom of well with 10 Sx cement from TD to 2833'.

Pull 4 1/2" to 225' and displace 25 Sx cement. Pull 4 1/2", set bridge and 10 Sx cement to bottom of cellar.

Very truly yours,

H. L. Nichols
 Conservation Division Agent